



GENERAL NOTES:

1. GRANULAR TRENCH BACKFILL SHALL BE MECHANICALLY COMPACTED IN LAYERS OF 12" MAXIMUM, LOOSE MEASURE, TO 95% OF STANDARD MAXIMUM DENSITY (ASTM D 698)
2. EXCAVATED MATERIAL USED FOR BACKFILL SHALL BE MECHANICALLY COMPACTED IN LAYERS OF 18" MAXIMUM, LOOSE MEASURE, TO 90% OF STANDARD MAXIMUM DENSITY (ASTM D 698)

NOT TO SCALE

REV:	KLM	DATE:	10/12/2006
REV:	RMS	DATE:	07/2004
DRAWN BY:	VIV	DATE:	01/2003

PIPE INSTALLATION

VILLAGE OF VILLA PARK  
SANITARY - 08